

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.  
Wichita, KS 67202

API Number 15- 147-20,304-00-00 ✓

Operator's Full Name GEODESSA CORPORATION

Complete Address 1125-17<sup>th</sup> ST. 2220 DENVER, COLORADO.

Lease Name BECHER (Hoffman) Well No. H-#1.

Location E-NW-NE Sec 22 Twp. 4 Rge. 20 (East) (West)

County PHILLIPS Total Depth 3605 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor PIONEER DRILL, INC. (DON ARMBRUSTER)

Address 308 WEST MILL PLANNVILLE, Mo. License No. \_\_\_\_\_

Operation Completed: Hour: 12:00 PM Day: 21<sup>st</sup> Month: MARCH Year: 19 81

The above well was plugged as follows:

8 5/8" 248 FE SP CUC w/ 165 SF COMMON-2% GEL-3% CM-CL.  
ORDERED 110 SF 50/50 BZMIX 6% GEL. + 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>st</sup> PLUG. @ 920 FE w/ 65 SF CNT.  
2<sup>ND</sup> PLUG. @ 270 FE w/ 30 SF CNT.  
3<sup>RD</sup> PLUG. → SOLID BRIDGE @ 40 FE to 0 w/ 10 SF  
5<sup>th</sup> IN RAT HOLE.

CEMENTED BY SUN CNT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 24 1981 3-24-81

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Marion Schmidt  
Conservation Division Agent

DATE 4-27-81

INV. NO. 5291-W

15-147-20304-00-00

WELL LOG

OPERATOR: Geodessa Corporation

WELL NAME: Becker "A" #1 LOCATION: C NW NE 23-4s-20W

COUNTY: Phillips STATE: Kansas

WELL COMMENCED: March 14, 1981 WELL COMPLETED: March 21, 1981

ELEVATION: 2095' G.L. TOTAL DEPTH: 3605'

PRODUCTION: D & A RIG NO: Rig #4

CASING - 8 5/8": 248.61' new 28# cemented with 165 sxs common 3% cc 2% gel did circ  
P.D. @ 6:45 A.M. 3-14-81  
5 1/2": \_\_\_\_\_

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	256'	sand	256' - 3/4 - degree	
256'	606'	sand		
606'	1605'	sand and shale		
1605'	1649'	sand and shale		
1649'	1681'	Anhydrite		
1681'	2006'	sand and shale	2006' - 1 - degree	
2006'	2310'	shale and lime		
2310'	2565'	lime and shale		
2565'	2816'	shale and lime		
2816'	2988'	shale and lime		
2988'	3163'	lime and shale		
3163'	3315'	shale and lime		
3315'	3319'	shale and lime	3319' - 3/4 - degree	
3319'	3336'	shale and lime		
3336'	3346'	shale and lime		
3346'	3437'	lime and shale		
3437'	3552'	lime and shale		
3552'	3605'	lime and shale		
3605'	RTD			

RECEIVED  
STATE CORPORATION COMMISSION

MAR 27 1981  
3-27-81

REGISTRATION DIVISION  
Topeka, Kansas

STATE OF KANSAS  
COUNTY OF \_\_\_\_\_

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

PIONEER DRILLING CO., INC.

By Connie Jo Austin

SUBSCRIBED AND SWORN TO, BEFORE ME, This 26<sup>th</sup> day of March, 1981

Judy Smith  
NOTARY PUBLIC

