

To: **6 010744**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Operator: Petroleum Mgmt Inc.
Name & Address 400 N. Woodland #201
Wichita, Ks. 67208

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☒ SWD Well ☒ D&A ☐

Other well as hereinafter indicated ☐

Plugging Contractor P. M. I. License Number

Address Same

Company to plug at: Hour: 10:00AM Day: 25 Month: Jan Year: 19 91

Plugging proposal received from Don Keener

(company name) Same (phone)

were: Shoot casing at 1520 anhydrite and at base dakota 970.

Order 50 sks common cement, 350 sks 65/35 poz 8% gel and 300 lbs. hulls.

Run tubing to 3000 . 4 1/2 casing at 3433. Perf 3168 - 3344.

top dakota 667. top anhydrite 1510.

Plugging Proposal Received by D. F. B. (TECHNICIAN)
2-13-91

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 1:30PM Day: 25 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Pumped down tubing 50 sks common cement.

Pulled tubing to 2600. Pumped down 100 sks 65/35 poz 8% gel; pulled tubing to

1200. Pumped down 60 sks 65/35 poz 8% gel. Circulated. Laid down tubing.

Pumped down 4 1/2 casing 50 sks 65/35 poz 8% gel Max pres. 500 lbs. Closed w/200 lbs

Pumped down 8 5/8 100 sks w/200 lbs. hulls. Max pres. 1100 lbs. Closed w/900 lbs

Pumped down 4 1/2 casing 40 sks w/100 lbs. hulls. Max pres. 600 lbs.

Remarks: Allied Cement Co. Closed w/400 lbs. pres.

Additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

DATE 2-22-91

INV. NO. 30816

Signed Dale F. Baltazar (TECHNICIAN)