

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20308-00-01
Spot: NENWSE Sec/Twnshp/Rge: 10-4S-19W
2260 feet from S Section Line, 1800 feet from E Section Line
Lease/Unit Name: FLANIGAN Well Number: 8
County: PHILLIPS Total Vertical Depth: 3430 feet

Operator License No.: 31569 Conductor Pipe: Size feet: 3 1/1.48
Op Name: BACH, JASON DBA BACH OIL PRODUCT Surface Casing: Size 8.625 feet: 239 w/150 sxs cmt
Address: RR 1, BOX 28 Production: Size 4.5 feet: 3428 w/160 sxs cmt
PHILLIPSBURG, KS 67661 Liner: Size feet:

Well Type: EOR UIC Docket No: E16225.4 Date/Time to Plug: 11/08/2002 8:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 476-5254

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 600# hulls.
Casing squeezed below 2000' - not drilled out.
Multiple holes followed with 400' to 2000'.
W.L.M. 2000' T.O.C.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/08/2002 9:45 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementers to 4 1/2" casing.
Squeezed 200 sxs 60/40 pozmix - 10% gel plus 500# hulls mixed in cement.
Max. P.S.I. 600#. S.I.P. 200#.
R.U. Cementers to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 100#.

RECEIVED
DEC 03 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

INVOICED

Form CP-2/3


DATE 12-3-02
VV. NO. 2003060894

NOV 27 2002

10-4-19W
 50'S&150'W,
 NE. NW SE

PETROLEUM MNGMT., INC. #8 FLANIGAN
 400 N. WOODLAWN, #201 WICHITA, KS 67208
 CONTR RED TIGER DRG. CO. CTV PHILLIPS

GEOL _____ FIELD BECKMAN
 E 1962 KB CM 1/30/81 CARD ISSUED 5/28/81 P 36 BOPD & WTR



API 15-147-20,308

SMP	TOPS	DEPTH	DATUM
ANH		1471	+ 491
B ANH		1502	+ 460
HEEB		3121	-1159
TOR		3146	-1184
LANS		3166	-1204
B KC		3384	-1422
RTD		3430	-1468

8-5/8" 239/150sx, 4 1/2" 3428/160sx
 NO DST'S
 MICT - CO, PF 3339-44, 3321-25,
 3265-69, 3250-54, 3243-46, 3201-11,
 AC 2500 GAL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS