

6040490

15-147-20106-00-00  
API NUMBER 15-

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NESWSW, SEC. 10, T. 4 S, R. 19 W/4  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name Roeder Well # 1

Operator Name & Address Pet. Mgmt. Inc.

County Phillips 112.29

Address 400 N. Woodlawn

Well Total Depth 3455 feet

S. 201

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Wichita, Ks 67208

Surface Casing: Size 8 3/8 feet 193' w/150

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Emty License Number \_\_\_\_\_

Address Hays, Ks

Company to plug at: Hour: 4:30 PM Day: 24 Month: 10 Year: 19 85

Plugging proposal received from Wayne Fuzzell

(company name) P. M. I. (phone) \_\_\_\_\_

were: 4 1/2" csg set @ 3476' w/250 sx cmt.

Perf @ 3174-78 - 3228-32 - 3248-52 - 3263-69

3340-44 Holes in csg @ 1060' & also 1489'

Ordered 300 sx 6 3/4 P.S.I. 690 gel, - 30 sx gel

8 sx hulls & 4 1/2" w. plug

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4:30 PM Day: 24 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT pumped in 4 1/2" csg 325 sx cmt w/hulls,

→ 10 sx gel w/hulls, <sup>Rel. plug</sup> 5 1/25 sx cmt w/hulls

P.S.I. 500#

pumped in 8 3/8 S.P. → 50 sx cmt w/hulls, →

10 sx gel w/hulls, → 50 sx cmt w/hulls → 10 sx

gel w/hulls, → 50 sx cmt. P.S.I. 400#

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 22 1985

INV. NO. 1146

observe this plugging.  
STATE CORPORATION COMMISSION

NOV 8 1985  
11-8-85

CONSERVATION DIVISION  
Wichita, Kansas

Signed Dennis L. Hamel  
(TECHNICIAN)

FORM CP-2/3 11-7-85  
Rev. 01-84