

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Operator: Petroleum Mgmt. Inc.  
Name & Address 400 N. Woodlawn  
Wichita, Kansas

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Petroleum Management Inc. License Number 5242

Address 400 N. Woodlawn, Wichita, Kansas

Company to plug at: Hour: \_\_\_\_\_ Day: 16 Month: 5 Year: 19 88

Plugging proposal received from Don Keener

(company name) Petroleum Management Inc. (phone) \_\_\_\_\_

were: Order 50 sx common cem, 250 sx cem. 65/35 pozmix, 10% gel., 2% lite, 600# hulls,  
60# flocl. 5 1/2" casing @ 3409, no recovery. 5 1/2" casing perf @ 3162-3312'. DV @ 370  
w/250 sx cem. 5 1/2" perf @ 1500'

Plugging Proposal Received by Dale Balthazor

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 16 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT Pressurized up 8 5/8", locked @ 400#. Pumped down 5 1/2" casing 50 sx  
common cem. then 100 sx 65/35, on vacuum, then 150 sx 65/35 w/300# hulls. Maximum pressure  
900#, Closed in w/450#.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Allied Cementing Co.

(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 6-22-88  
INV. NO. 20934

JUN - 1 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Dale Balthazor  
(TECHNICIAN)  
Dale Balthazor

5-16-88  
API NUMBER 15- 147-20,146  
SE NE NW, SEC. 30, T 4 S, R 19 W/8  
00-01 R

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Lease Name Adee Well # 4-SWD

County Phillips 110.83

Well Total Depth 3410 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 180

Input Well EOR KCC SWD Well X X D&A