

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-16
API NUMBER 15- 147-20,147-0000

NW SE NW, SEC. 30, T. 4 S, R. 19 W/Ex
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242
Operator: Petroleum Mgmt. Inc.
Name & Address: 400 N. Woodlawn
Suite 201
Wichita, Ks. 67208

Lease Name Adee Well # 5
County Phillips 111.15
Well Total Depth 3420 feet
Conductor Pipe: Size _____ feet

Abandoned Oil Well Gas Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____
Address Russell, Ks.

Company to plug at: Hour: 5:45PM Day: 16 Month: May Year: 19 88

Plugging proposal received from Wayne Fuzzell

(company name) Pet. M. I. (phone) _____

were: Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/1/2# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45PM Day: 16 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 4 1/2" set at 3418' w/250 sks. Top perf at 3168'.

Plugged bottom 3120' w/sand and 4 sks cement to 3120'. Shot pipe at 1505', 1200', 832',
and recovered 832'. Pumped in 8 5/8", 250 sks A.T.L. w/1/2# F.C. plus 6 sks Hulls in cement
Max 800# psi. Shut in 300# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 10-25-88
INV. NO. 22715

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel