

15-053-19014-00-00 Kcap

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-25154-00-00
Spot: SESESE Sec/Twnshp/Rge: 12-17S-10W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: PLOOG Well #: 1
County: ELLSWORTH Total Vertical Depth: 3251 feet

Operator License No.: 3309
Op Name: EAGLE PETROLEUM, INC.
Address: PO BOX 106
BUSHTON, KS 67427

PROD Size: 5.5 feet: 3240
SURF Size: 8.625 feet: 214

\$105⁶⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2004 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
AUG 25 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/19/2004 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2450' and put 5 sacks of cement on top. Perforated at 1250', 950', and 270'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 950' and pumped 35 sacks of cement. Pulled tubing to 270' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3102	3107		
2506	2516		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT #24612

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 8-31-04
INV. NO. 2005060460