

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21764-00-01
Spot: NENENW Sec/Twnshp/Rge: 4-16S-26W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: THORNBURG F Well #: 1
County: NESS Total Vertical Depth: 4575 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: PO BOX 2758 221 N MAIN STE 300
WICHITA, KS 67201

PROD Size: 4.5 feet: 4574 WITH 300 SX CMT
SURF Size: 8.625 feet: 323 WITH 200 SX CMT

148

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2004 11:30 AM
Plug Co. License No.: 5144 Plug Co. Name: MULL DRILLING COMPANY, INC.
Proposal Rcvd. from: JIM Company: MULL DRILLING COMPANY, INC. Phone: (316) 264-6366

Proposed Plugging Method: SAND PERFS 50' ABOVE TOP PERF. PUMP 30 SX CMT W/3% CC AT 1600'. PERFORATE AT 1200'. PUMP 80 SX CMT OVER CASING VOLUME. IF IT DOES NOT CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2004 3:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CASING LEAK @ 1572-1603'. SQUEEZED WITH 250 SX CMT. SAND TO 4430' WITH 7 SX CMT ON TOP. SPOT 30 SX CMT WITH 3% CC AT 1630'. PULL TUBING OUT OF HOLE. WAIT 1 1/2 HOURS. PERFORATE CASING AT 1200'. PUMP DOWN 4 1/2" WITH 150 SX CMT. SHUT IN PRESSURE 700#. PUMP PRESSURE 900#. HOOK ONTO BACKSIDE & PUMP 35 SX CMT. SHUT IN PRESSURE 400#.

Perfs:


Top	Bot	Thru	Comments
4500	4512		
4494	4520		

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

RECEIVED
OCT 04 2004
KCC WICHITA

District: 01



Signed

[Signature]
(TECHNICIAN)

INVOICED
DATE 10-4-04
INV. NO. 2005060585

Form 11/2/3