

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20770-00-01  
Spot: SWNE Sec/Twnshp/Rge: 14-35S-12W  
3300 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: GOTTSCH-PETERMANN OW Well #: 2  
County: BARBER Total Vertical Depth: 4918 feet

Operator License No.: 6006  
Op Name: MOLZ OIL COMPANY  
Address: 19159 S.W. CLAIRMONT  
KIOWA, KS 67070

CIBP Size: feet: 4700 WITH 2 SX CMT  
PROD Size: 5.5 feet: 4918 WITH 150 SX CMT  
SURF Size: 8.625 feet: 323 WITH 300 SX CMT

4159

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2004 2:00 PM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 40 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: NONE

Date/Time Plugging Completed: 09/27/2004 4:00 PM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4859	4868		
4840	4858		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 5 1/2" CASING.

Plugged through: CSG

RECEIVED  
OCT 04 2004  
KCC WICHITA

District: 01

RECEIVED  
SEP 29 2004  
KCC Dodge City

Signed

*[Signature]*  
(TECHNICIAN)

INVOICED

DATE 10-4-04  
2005060584

Form CP-273  
*[Signature]*