

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20465-00-00
Spot: SWSNW Sec/Twnshp/Rge: 21-34S-21W
2310 feet from N Section Line, 3630 feet from E Section Line
Lease Name: SHUPE Well #: 1-21-A
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

CIBP Size: feet: 4150 WITH 2 SX CMT
COND Size: 20 feet: 120 WITH 350 SX CMT
PROD Size: 4.5 feet: 4394 WITH 175 SX CMT
SURF Size: 8.625 feet: 872 WITH 800 SX CMT

\$143⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2004 1:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4150' WITH 2 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: NONE
Date/Time Plugging Completed: 09/28/2004 11:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4345'. CIBP @ 4150' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG SPOT 50 SX CMT AT 900'. 2ND PLUG PULL TO 400' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4264	4274		

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 3418' OF 4 1/2" CASING.

Plugged through: CSG

RECEIVED
OCT 04 2004
KCC WICHITA

District: 01



Signed

[Signature]
(TECHNICIAN)

INVOICED
DATE 10-4-04
INV. NO. 2005060583

Form CP-2/3