

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21596-00-01
Spot: SESESE Sec/Twnshp/Rge: 7-30S-15W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: LEE TRUST Well #: G-1
County: BARBER Total Vertical Depth: 2290 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 4.5 feet: 2285 WITH 150 SX CMT
SURF Size: 8.625 feet: 1140

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/24/2004 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 2000' & 4 SX CMT. FREEPOINT CASING & PULL TO 1170'. SPOT 10 SX GEL & 50 SX CMT. PULL CASING TO 300' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2004 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:


SANDED BACK TO 2000' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1170' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
SEP 30 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1845' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-2/3