

15-147-20106-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Roeder

WELL NUMBER 1

990 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 10 TWP. 4S RGE. 19 (~~W~~) (W)

COUNTY Phillips

Date Well Completed 10/2/70 *original*

Plugging Commenced 10/24/85

Plugging Completed 10/24/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, KS

Is ACO-1 filed? N/A If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top 3188' Bottom 3344' T.D. 3455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-------------|---------|------|-------|--------|---------|------------|
| Kansas City | Water | 0 | 3476' | 4 1/2" | 10/2/70 | -0- |
| | | 0 | 193' | 8 5/8" | 10/2/70 | -0- |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

4 1/2" casing plugged as follows: 25 sacks 60/40 pozmix, 10 sacks gel, 4 1/2" wiper plug and 125 sacks cement. 4 sacks hulls mixed in whole treatment.
8 5/8" casing plugged as follows: 50 sacks 60/40 pozmix, 10 sacks gel, 50 sacks cement, 10 sacks gel, 50 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address 400 N. Woodlawn, Suite 201, Wichita, KS 67208

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Dale Silcott

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Dale Silcott

(Address) 400 N. Woodlawn, Suite 201
Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 85

Bonnie Brown
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
Expires: 10-31-85



OCT 31 1985

CONSERVATION DIVISION