

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-2018-00-01
API NUMBER N/A

LEASE NAME Beckman

WELL NUMBER 2

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 10 TWP. 4S RGE. 19 ~~6E~~ (W)

COUNTY Phillips *original*

Date Well Completed March 71

Plugging Commenced 1/25/91

Plugging Completed 1/25/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PETROLEUM MANAGEMENT, INC.

ADDRESS 14201 E. Central - Wichita, KS 67230

PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 24, 1991 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? NO - ATTACHED TO PLUGGING APPLICATION

Producing Formation Kansas City Depth to Top 3168' Bottom 3400' T.D. 3434'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>CASING/KC</u>	<u>OIL AND WATER</u>	<u>3180</u>	<u>3400</u>	<u>8 5/8</u>	<u>208</u>	<u>0</u>
				<u>4 1/2</u>	<u>3433</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped down tubing 50 sks common cmt. Pulled tubing to 2600'. Pumped down 100 sks 65/35 poz 8% gel; pulled tubing to 1200'. Pumped down 60 sks 65/35 poz 8% gel. Circulated. Laid down tbg. Pumped down 4 1/2 casing 50 sks 65/35 poz 8% gel Max Pres. 500 lbs. Closed w/200 lb. Pumped down 8 5/8 100 sks w/200 lbs hulls. Max pres. 1100 lbs. Closed w/900 lb.
(If additional description is necessary, use BACK of this form.) Over-----

Name of Plugging Contractor Petroleum Management, Inc. License No. 5242

Address 14201 E. Central - Wichita, KS 67230

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc. *FEB 28 1991*

STATE OF KANSAS COUNTY OF SEDGWICK, ss. *2-28-91*

Steven P. O'Neill (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Steven P. O'Neill*

(Address) 14201 E. Central-Wichita, KS 67230

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1991

My Commission Expires



Notary Public

Pumped down $4\frac{1}{2}$ casing 40 sks w/100 lbs. hulls. Max pres. 600 lbs. Allied Cement
Co. closed w/400 lbs. pressure.