

15-147-3041-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Phillips County. Sec. 10 Twp. 4S Rge. 19W (E) (W)
Location as "NE/CNW/SW" or footage from lines. C NW NW
Lease Owner Sierra Petroleum Company, Inc.
Lease Name Bach Well No. 1
Office Address 211 N. Broadway - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 26, 1966
Application for plugging filed November 26, 1966
Application for plugging approved November 26, 1966
Plugging commenced November 26, 1966
Plugging completed November 26, 1966
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3335 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	216'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 540' w/20 sx
cement. Set plug @ 210'
w/20 sx cement. Set plug
@ 40' w/8 sx cement.
2 sx cement in rathole.

RECEIVED
NOV 27 1966
CONSERVATION DIVISION
Wichita, Kansas
12-3-66

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Maxine V. Starr (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr
1720 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1966

My commission expires 5-22-70

Jean Sheehan
Notary Public.

18-147-30141-0000

DRILLERS LOG

Bach No. 1

CASING RECORD: 8 5/8" @ 216' w/140 sx cement

COMPANY: Sierra Petroleum Co., Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: November 21, 1966

COMPLETED: November 26, 1966

DESCRIPTION: C NW NW 10-4S-19W Phillips Co., Ks.

ELEVATION:

TOTAL DEPTH: 3335'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	585	<p>RECEIVED STATE CORPORATION COMMISSION DEC 5 1966 12-5-66 CONSERVATION DIVISION Wichita, Kansas</p>
Shale & Sand	585	800	
Sand	800	840	
Hard Sand	840	856	
Shale	856	1000	
Sand	1000	1200	
Shale	1200	1481	
Anhydrite	1481	1510	
Shale	1510	2110	
Shale & Lime	2110	2995	
Lime	2995	3335	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 29th day of November, 1966.

Jean Stollar
Notary Public

My Commission Expires:

5-22-70