

15-147-20348-06-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Phillips SEC. 24 TWP. 4S RGE. 19W E/W
 Location as in quarters or footage from lines:
1850' NSL, 1090' EWL SE/4

Lease Owner Viking Energy Management Co.
 Lease Name E & L PARKER Well No. 1
 Office Address 2761 E. Skelly Dr., Tulsa, OK 74105
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed August 26, 1981
 Application for plugging filed August 26, 1981
 Plugging commenced August 26, 1981
 Plugging completed August 26, 1981
 Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Locate Well
 correctly on above
 Section Platt.

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 840' with 70 sx.
Set 2nd plug @ 210' with 40 sx.
Set 3rd plug @ 40' with 10 sx.
5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.
Job complete @ 7:00 a.m., 8/26/81.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
 801 Union Center, Wichita, KS 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 1981

My Commission expires: 7-13-85

Elizabeth G. Terry Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION
 SEP 10 1981
 9-10-81
 CONSERVATION DIVISION
 Wichita, Kansas



15-147-20348-00-00

CONTRACTORS WELL LOG

OPERATOR:	Viking Energy Management Co.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	E & L PARKER #1
LOCATION:	1850' NSL 1090' EWL SE/4 Phillips County, Kansas
SPUD DATE:	8/20/81
COMPLETION DATE:	8/26/81

0	1430	Sand & Shale
1430	1677	Shale
1677	1850	Shale & Sand
1850	2646	Shale
2646	3310	Shale & Lime
3310	3390	Lime
	3390	Rotary Total Depth

Spud hole @ 10:15 p.m., 8/20/81. Drilled 246' of a 12¼" hole. Ran 6 jts. of 8 5/8" 20# casing set @ 242.63' and cemented with 170 sx. common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 4:20 a.m., 8/21/81.

3390' TD. Set 1st plug @ 840' with 70 sx. Set 2nd plug @ 210' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c. Job complete @ 7:00 a.m., 8/26/81.

SAMPLE TOPS:

Anhydrite	1432'
B/Anhydrite	1499'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the E & L PARKER #1, 1850' NSL 1090' EWL SE/4, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 3rd day of September, 1981.

Elizabeth G. Terry
Elizabeth G. Terry
NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 10 1981
 9-10-81
 CONSERVATION DIVISION
 Wichita Kansas

