

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-20126-00-01

API NUMBER N/A

LEASE NAME Schneider "A"

WELL NUMBER 1

4950 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 30 TWP. 4 RGE. 19 XX or (W)

COUNTY Phillips

Date Well Completed 7/71

Plugging Commenced 5/14/87

Plugging Completed 5/14/87

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? Already submitted with plugging application.

Producing Formation Lansing/K.C. Depth to Top 3139' Bottom 3206' T.D. 3491'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/K.C.	Oil	0	3393'	5 1/2"	3393'	1200'
		0	224'	8 5/8"	224'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 200 sx 35/65 Pozmix w/8 sx hulls down 8 5/8" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address P. O. Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1987

STATE CORPORATION COMMISSION

My Commission Expires:



Notary Public

JUN 3 1987

6-3-87

CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 08-84

DRILLERS LOG

No. 1 Schneider "A"

CASING RECORD: COMPANY: Petroleum Management, Inc. DESCRIPTION:
8 5/8" @ 224' CONTRACTOR: Red Tiger Drilling Co. NW NE NE
w/160 sx cement COMMENCED: July 13, 1971 30-4S-19W
5 1/2" @ 3393' COMPLETED: July 21, 1971 Phillips County,
w/200 sx cement Kansas
TOTAL DEPTH: 3491' ELEVATION:


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & shale	0	225	
Shale, sand, redbed	225	1493	
Anhydrite	1493	1523	
Shale	1523	2030	
Shale & lime	2030	2965	
Lime, chert	2965	2985	
Lime	2985	3455	
Arb. Dolo.	3455	3491	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 9th day of August, 1971.



Virginia K. Albert
Notary Public

My Commission Expires:

July 23, 1974