

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD #4  
 K.A.R.-82-3-117

API NUMBER 15-147-20,145-00-00

LEASE NAME Adee

WELL NUMBER 3

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 30 TWP. 4S RGE. 19W CEX or (W)

COUNTY Phillips

Date Well Completed 3/10/72

Plugging Commenced 5/16/88

Plugging Completed 5/16/88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/2/88 (date)

by Shari Feist, Director (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing Formation Kansas City Depth to Top 3160' Bottom 3370' T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	oil			8-5/8"	202'	0
				5-1/2"	3409'	658'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Plugged bottom back with sand to 3075'. Put 5 sx cement on sand with dump bailer. Pumped down 8-5/8" with 250 sx 65/35 poz-10% gel-2% lite-1/4 lb. Flocele and 6 sx hulls. Shut in at 300 lb.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 5242

Address 400 N. Woodlawn, Suite 201, Wichita, Kansas 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven P. O'Neill

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 400 N. Woodlawn, Suite 201

Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 1st day of June, 19 88

[Signature]  
 Notary Public

My Commission Expires: 12-21-91

REBECCA WOLD  
 NOTARY PUBLIC  
 STATE OF KANSAS

My Appt. Exp. 12-21-91

RECEIVED  
 STATE CORPORATION COMMISSION

6-2-88  
 JUN Form 1684  
 Revised 07-87

CONSERVATION DIVISION  
 Wichita, Kansas