


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Phillips County, Sec. 30 Twp. 4 Rge. 19 (E) (WW)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner D. G. Hansen  
Lease Name Fox Well No. 3  
Office Address Logan, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 29 1960  
Application for plugging filed November 29 1960  
Application for plugging approved November 29 1960  
Plugging commenced November 29 1960  
Plugging completed November 29 1960  
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3405 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	172.53'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 400'. Set plug. Put in 20 sacks cement. Filled to 165'. Set plug. Put in 20 sacks cement. Filled with heavy mud up to 40'. Set Plug. Filled to top with 1 sack hulls and 10 sacks cement.

DEC 12 1960  
CONSERVATION DIVISION  
Wichita, Kansas

12-12-60

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C-G Drilling Co.  
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
107 Rule Building  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 1960

My commission expires May 20, 1963

Vicky Jacobs  
Notary Public.

15-147-00720-00-00

W E L L L O G

OPERATOR D. G. Hansen SEC. 30-4-19W  
 WELL NAME Fox #3 LOC. SW SW SW  
 TOTAL DEPTH 3405' COUNTY Phillips  
 COMM. November 23, 1960 COMP. November 29, 1960 STATE Kansas  
 RIG NO. 1 ELEVATION 1940' K.B.  
 CASING: Ran 172.53' (8 jts.) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	590	Shale-Sand		
590	740	Sand		
740	885	Sand-Shale		
885	1000	Sand		
1000	1240	Shale-Sand		
1240	1510	Shell-Shale		
1510	1552	Anhydrite		
1552	2160	Shale-Shell		
2160	2225	Shell-Shale	0° - 2500	
2225	2930	Shale-Lime	0° - 2750	
2930	3136	Lime-Shale	0° - 3000	
3136	3265	Lime	0° - 3250	
3265	3365	Lime-Shale		
3365	3405	Lime		

RECEIVED  
STATE OF KANSAS

DEC 12 1960

CO. DIVISION

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS.

12-12-60

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 5th day of December, 1960.

My commission expires:  
May 20, 1963

Vicky Jacobs  
Vicky Jacobs - Notary public