

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

053 01012

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
RECEIVED
WELL PLUGGING RECORD
K.A.R. 82-3-117
SEP 07 2004

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

19014-0000
KCC RP

API Number: 15-053-25154-00-00
Lease Name: Ploog
Well Number: 1
Spot Location (QQQQ): - SE - SE - SE
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 12 Twp. 17 S. R. 10 East West
County: Ellsworth
Date Well Completed: 5-12-1950
Plugging Commenced: 8-18-04
Plugging Completed: 8-19-04

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surf Prod				8-5/8"	214'	None
				5-1/2"	3240'	None

Show depth and thickness of all water, oil and gas formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.
Plugged off bottom with sand to 2450' and 5 sacks cement, perforated well @1250', 950' and 270'. Ran 2" tubing to 1250', pumped 35 sacks cement, pulled to 950', pumped 35 sacks cement, pulled to 270', pumped 70 sacks cement. Ran 1" tubing down 8-5/8" to 240' and circulated 60 sacks cement to top, 60/40 pos, 4% gel. Plugging Complete..

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Eagle Petroleum, Inc.
State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 2nd. day of September, 2004

My Commission Expires: _____
NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

01013-NE #2

[Handwritten signature]