

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: K & N Petroleum
 Address: 513 West 6th Street, Ellinwood, Kansas 67526
 Phone: (620) 564-3422 Operator License #: 3208
 Type of Well: EDR Docket #: 22,507
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) 7-8 (If SWD or ENHR)
 The plugging proposal was approved on: September 13th, 2004 (Date)
 by: Jack Luthi (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: 3081' Bottom: 3258' T.D. 3329'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 159-20,175 - 00-01
 Lease Name: Mansz
 Well Number: #1
 Spot Location (QQQQ): SW - NE - NE -
4290' Feet from North / South Section Line
990' Feet from East / West Section Line
 Sec. 17 Twp. 19 S. R. 10 East West
 County: Rice
 Date Well Completed: 11/11/1968 *orig Spud well date*
 Plugging Commenced: 9/14/04
 Plugging Completed: 9/16/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	213'	8-5/8"	213'	0'
	Production	0'	3316'	5-1/2"	3316'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spotted sand on bottom - got all 80 bbls of water in hole. Rigged up Log Tech - perforated at 1300'; 850' and 270' - 2 holes per shot. Rigged Log Tech down.
 Rigged up Baker on sandline. Mixed 5 sx cement and spot on bottom with bailer. Made 4 trips in hole with bailer. Put cement at 3270'. Rigged down Baker. Ran 42, 2-3/8" joints of workstring. First plug - pulled 15 joints; 2nd plug - pulled 18 joints; 3rd plug - pulled remaining tubing. Rigged down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901


Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: K & N Petroleum

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 **KAREN J. MITCHELL**
Notary Public - State of Kansas
My Appt Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 22nd day of September, 20 04

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
RECEIVED
SEP 23 2004
KCC WICHITA
09-23-04