

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: 1201 Lake Robbins Dr, The Woodlands, TX 77380

Phone: (832) 636-3128 Operator License # 4549

Type of Well: D&A Docket # (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6/16/04 (Date)

by: Mike Maier (KCC District Agent's)

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number 15- 189-22468 -00-00

Lease Name Black Stone "A"

Well Number 1

Spot Location (QQQQ) CNW NW

660 Feet from [X] North / [] South Line of Section

660 Feet from [] East / [X] West Line of Section

Sec. 28 Twp. 34 S. R. 38 [] East [X] West

County: Stevens

Date Well Completed: N/A KCC

Plugging Commenced: 6/16/04 BEM

Plugging Completed: 6/16/04 10-4-04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Row 1: Surface casing, 0, 1769', 8-5/8", 1769', 0.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Spot 100 sxs of 40/60 POZ cement @ 3250'. spot 50 sxs @ 1780'. spot 40 sxs @ 720'. and 10 sxs 0-40' with heavy mud placed between each plug. Spot 15 sxs in rat hole and 10 sxs in mouse hole. Cut and cap 8-5/8" casing 4' below GL.

Name of Plugging Contractor: Murffin Drilling Co., Inc. License # 30606

Address 250 N. Water Street, Suite 300, Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Jerry N. Blossom (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God



(Signature) Jerry N. Blossom

(Address) 1201 Lake Robbins Dr., The Woodlands, TX 77380

SWORN TO before me this 1 day of October, 2004

Dawn D. Gardner My Commission Expires: 10. Aug. 2006