

4-032002

10-25

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-147-20,261-0000  
Near SE  
NW NW SW /4 SEC. 02, 04 S, 19 W  
2290 feet from S section line  
4930 feet from E section line

Operator license# 5252 Lease EHM well # 1

Operator: R.P. Nixon, Inc. County Phillips

Address: 207 West 12th Street  
Hays, Kansas  
Well total depth 3425 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 201 feet

111.31

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Jay-Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 25 Month: October Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon, Inc. Phone:    

Were: Order 325 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:30P.M., Day: 25, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 201'w/95 sxs. 4 1/2" set @ 3423'  
w/200 sxs. Prod. perfs. 3302' - 3379'. Critical area control shots at  
925' and 1500'. Squeezed 4 1/2" w/212 sxs. cement blend with 500# hulls  
mixed in to Max. P.S.I. 500#. Close in P.S.I. 200#.  
Squeezed 8 5/8" with 100 sxs.cement blend to Max. P.S.I. 100#. Close  
in P.S.I. 100#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 08 1994  
11-8-94

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks:  
Condition of casing(in hole):GOOD X BAD     Anhy.plug:YES X NO      
Bottom plug(in place):YES    , CALC X, NO     Dakota plug:YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did X ] observe the plugging. Carl Goodrow

DATE 11-9-94

(agent)

Form CP-2/3

INV. NO: 41625

10-25

INVOICED