

4-031999 10-24

E-20,066

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,377-0001

E2 NW SW /4 SEC. 02, 04 S, 19 W
1980 feet from S section line
4290 feet from E section line

Operator license# 5252 Lease EHM well # 3

Operator: R.P. Nixon, Inc. County Phillips

Address: 207 West 12th Street Well total depth 3450 feet
Hays, Kansas Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet

Aband. oil well __, Gas well __, Input well X, SWD __, D & A __

Plugging contractor: Jay-Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 24 Month: October Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon, Inc. Phone: _____

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.
50 sxs. common cement.
Allied Cement Company.
Order work string of tubing.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30A.M., Day: 24, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 212'w/80 sxs. 4 1/2" set @ 3448'
w/200 sxs. Prod. perms. 3279' - 3378'. Perf. at 1600' cwc. shot at
1546' by Bruce. Ran tubing to 2512' displaced 50 sxs. cement with 200#
hulls. Pulled to 1575' displaced 125 sxs. cement blend with 200# hulls.
Pulled tubing. Squeezed casing with a total of 50 sxs. common cement
and 175 sxs. cement blend to Max. P.S.I. 500#. Close in P.S.I. 500#.
Tested 8 5/8" to 300# cement at surface. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: No Docket Number - too old.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO NOV 0 8 1994
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO 11-08-94
Plugged through TUBING, CASING. Elevation: (GL CONSERVATION DIVISION
WICHITA, KANSAS)

I did [X] / did not [] observe the plugging. Carl Goodrow

INVOICED
DATE 11-9-94
INV. NO. 41629
10-24

(agent)
Form CP-2/3