

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-147-20,421-00-00  
SW4, Sec. 6, T 4 S, R 19 W/E  
990 feet from N(S) section line  
3300 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923

Lease Name Zillinger Well # 1

Operator: American Petroleum  
Name & Address: S. 111 - 400 N. Woodlawn  
Wichita, KS, 67208

County Phillips

Well Total Depth 3505 feet 113.91

Conductor Pipe: Size - feet -

Surface Casing: Size 8 1/2 feet 241 w/120sx

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Contg License Number

Address Russell, Kan.

Company to plug at: Hour: 11:30 AM Day: 30 Month: 5 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Mitchell Kelso

(company name) Kelso cog. (phone)

were: 4 1/2" csg @ 3505' w/ 500 sx - Top Perf. 3341'

P. B w/ 4 sx cmt. -> sand to 3300' -> 4 sx cmt.

Recovered 1625' of 4 1/2" csg

Ordered 190' 50% poz - 8% gel - 3% cc; 25 sx. gel; 6 sx  
hulls; + 8 1/2" W. Plug.

Signed Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:00 pm Day: 30 Month: 5 Year: 1984

ACTUAL PLUGGING REPORT

Impd in 8 1/2" -> 2 sx hulls -> 40 sx cmt. w/ 120 sx hull  
-> 100 sx cmt w/ 1 hull -> 15 sx gel w/ hull -> R. Plug -> 50 sx cmt

Max. P.S.I. 600 #

Shut-in P.S.I. 100 #

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 04 1984  
6-4-84  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 6-5-84

INV. NO. 1792