

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,276
Near NE NE SE /4 SEC. 03, 04 S, 19 W
2280 feet from S section line
3090 feet from E section line

Operator license# 5252 Lease Beckman well # 1

Operator: R.P. Nixon, Inc. County Phillips 11131

Address: 207 West 12th Street Well total depth 3425 feet
Hays, Kansas Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 236 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Jay-Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 25 Month: October Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon, Inc. Phone: _____

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:30P.M., Day: 25, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 236'w/100 sxs. 4 1/2" set @ 3424'
w/150 sxs. Prod. perfs. 3226' - 3384'. Critical area control shots at
925' and 1500'. Squeezed 4 1/2" w/288 sxs. cement blend with 500# hulls
mixed in to Max. P.S.I. 500#. Close in P.S.I. 250#.
Squeezed 8 5/8" with 25 sxs. cement blend to Max. P.S.I. 500#. Close
in P.S.I. 500#. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

NOV 08 1994

Remarks: _____
Condition of casing(in hole):GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did observe the plugging. Carl Goodrow

INVOICED
DATE 11-9-94
INV. NO: 41628
10-25

(agent)