

6 010681

9-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 147-20,227 - 00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Operator: Petroleum Management Inc.
Name & Address: 400 N. Woodlawn
Wichita, Ks.

SW SE SE, SEC. 3, T 4 S, R 19 W&E
330 feet from S section line
990 feet from E section line

Lease Name Beckman Well # B-1

County Phillips 111.96
Well Total Depth 3445 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor P.M.I. License Number 5242

Address Same

Company to plug at: Hour: Day: 22 Month: Sept Year: 19 89

Plugging proposal received from Don Keener

(company name) P.M.I. (phone)

were: Perf Dakota at 967' and anhydrite at 1527'.
4 1/2" at 3444'. Run wireline to T.D.

Order 350 sks cement 65/35 poz 8% gel 500# hulls.

Plugging Proposal Received by D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 22 Month: Sept Year: 19 89

ACTUAL PLUGGING REPORT Ran wireline to 3382' Perf casing at 1527' and

967'. Pumped down 4 1/2" casing 200 sks cement w/250# hulls. Max pres. 700#. Closed 200#.

Pumped down 8 5/8" 100 sks cement w/250# hulls. Max pres. 1000#. Closed 600#. Pumped down

4 1/2" casing 50 sks cement. Max pressure 1200#. Closed w/300# pres.

Remarks: Elt perf. Allied Cement Co.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-25-89
INV. NO. 26234
9-22 DEC 15 1989

Signed Dale F. Balthazor
(TECHNICIAN)
Dale F. Balthazor