

6

010641

10-12

400 K

API NUMBER 15-147-19086-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE SW, SEC. 3, T 4 S, R 19 W/4E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134 Lease Name Beckman Well # B-1

Operator: Graham Michaelis Corp County Phillips
Name & Address: Box 247
Wichita, Ks. 67201. Well Total Depth 3430 feet

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1988
11/8-88
CONSERVATION DIVISION
Wichita, Kansas

111.48

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor _____ Same _____ License Number 5143

Address _____ Same _____

Company to plug at: Hour: _____ Day: 12 Month: Oct Year: 19 88

Plugging proposal received from Norman

(company name) Same (phone) _____

were: Order 400 sks cement 65/35 Poz 6% Gel 500# Hulls. Perf at 1575' and 980'.

4 1/2" casing at 3429', 2 3/8" tubing parted at 1640'. Ran wireline to 1680'.

4 1/2" casing. Perf 3239' to 3353'.

Elev. 2029' Anhydrite 1565'

S.L.D. 1350'

Top 679' = 980' Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 12 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Fluid level at 200'. Ran perf gun to 1140'. Stuck. Came out of

hole. Pumped down 30 Bbls water. Ran perf gun to 1140'. Stuck. Shot three holes at 1140'.

Shot three holes at 980'. Pumped down 4 1/2" casing 50 sks cement then 125 sks cement w/150#

Hulls. Max pressure 800#. Holding 400#. Pumped down 8 5/8" casing 125 sks cement w/150# Hulls.

Max pressure 1000#. Holding 900#.

Remarks: Allied Cement Co.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 11-9-88

Signed Dale F. Balthazor (TECHNICIAN)

INV. NO. 22953