

6010404

API NUMBER 15- old well

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-SE-NW, SEC. 3, T 4 S, R 19 W
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5252
Operator: R.P. Nixon Oper.
Name & Address: 207 W 12th
Hays Ks.

Lease Name Bishop Well # 1
County Phillips 111.77
Well Total Depth 3439 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor R.P. Nixon License Number 5252
Address Hays Ks

Company to plug at: Hour: 9:30 A Day: 11 Month: 10 Year: 19 85

Plugging proposal received from Paul Nixon
(company name) R.P. Nixon (phone) _____

were: order 150 sx cem. 60/40 pozmix 6% gel. 370. c.c.
20 sx. gel. - 3 sx hulls - 4 1/2 plug.

Dakota squared - No pipe recovery -
Perf Anhydrite @ 1550
4 1/2 log @ 3437 Part @ 3286-3357

Plugging Proposal Received by Dale Batthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11 AM Day: 17 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT Pumped down 8 5/8 150 SX cem. No pressure
Shut down on account of weather. Rain & mud.

Oct. 16- ordered 150 sx. cem. 60/40 6% gel. 10 sx gel. 4 1/2 plug.
25xhulls-pumped down 4 1/2 log. - 25 sx cem. - 1 sx hulls - 25 sx.
cem. - 10 sx gel. - 1 sx hulls - released plug. 100 sx cem.
closed 400^{ft} - tied into 8 5/8 press to 300^{ft}

Remarks: cem. co. B.J. Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 29 1985
INV. NO. 10756

RECEIVED
OCT 28 1985
CONSERVATION DIVISION
10-28-85

Signed Dale Batthazor (TECHNICIAN) 10-25-85