

4-041737 15-147-00445-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 4-2-62

12-14

C SW NE 1/4 SEC. 03, 04 S, 19 W  
660 300 feet from S section line  
1980 feet from E section line

Operator license# 5352

Lease: Beckman "B" Well # 1

Operator: Baird Oil Company, Inc.

County: Phillips 111.74

Address: Box 428  
Logan, Kansas 67646

Well total depth 3438 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 159 feet  
w/135 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: December Year 1995

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: 913-689-7456

Were: 4 1/2" casing set at 3438' w/200 sxs cement. Perf. at 3283' - 3360'. Anhy. at 1530'.  
Dakota at 1000'. W.L.M. at 3300'. T.O.F. at 1500'.  
Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls, plus 10 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 1:45 P.M., Day: 14, Month: December, Year: 1995

Actual plugging report: Pumped down 4 1/2" casing: 25 sxs cement with 200# hulls, followed  
with 10 sxs gel, followed with 150 sxs cement with 200# hulls. Max. P.S.I. 300#. S.I.P.  
200#. Pumped down 8 5/8" S.P. 25 sxs cement with 100# hulls. Max. P.S.I. 300#.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC X, NO  
Plugged through TUBING, CASING X. Elevation: GL  
Anhy. plug: YES X NO  
Dakota plug: YES X, NO

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

INVOICED  
DATE 1-8-96  
INV. NO. 44425

110

STATE CORPORATION COMMISSION  
DEC 26 1995  
12-26-95