

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19499-00-00
Spot: SESESW Sec/Twnshp/Rge: 28-25S-5E
450 feet from S Section Line, 2935 feet from E Section Line
Lease Name: BURLINGAME-STOKES A Well #: 38
County: BUTLER Total Vertical Depth: 2474 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

CIBP Size: feet: 2100
PROD Size: 7 feet: 2464 160 SX CMT
SURF Size: 10.75 feet: 50 35 SX CMT

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 11 2004

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2004 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

CONSERVATION DIVISION
WICHITA, KS

\$ 80 41

Proposed Plugging Method: RUN TUBING TO 1970'. MIX AND PUMP 125 SX CLASS A, 3% CC. PULL TBG. WIRELINE TAG CEMENT HAVE AT LEAST 1620' TOP. PERF AT 275'. TRY TO PUMP 65/35 POZMIX, 4% GEL IN IF TIGHT, PERF ABOVE 145' OLD SQUEEZE @ 100', TRY TO CIRCULATE CEMENT TO SURFACE. IF TIGHT LAND 7" TIE ONTO 10-3/4 NIPPLES TRY TO PUMP CEMENT.

RECEIVED
KCC DISTRICT #2

OCT 6 - 2004

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 05/11/2004 12:00 AM KCC Agent: DONALD HOBERECHT

WICHITA, KS

Actual Plugging Report:

5/6/2004 -- Ran tubing to 1985' and pumped 125 sacks of Class "A" cement with 3% CC. Pulled tubing to surface. Tagged cement with wireline at 1325'. Perforated 7" casing at 275'. Ran packer on tubing to 220'; could not pump in. Shot 7" casing at 100'. Ran packer on tubing to 65'. Pumped 50 sacks of 60/40 posmix with 4% gel and circulated cement to surface. Pulled tubing and topped off with 35 sacks of cement. United #5436.
5/11/2004 -- Ran tubing to 210' and tagged top of cement in 7" casing. Pumped 50 sacks of 60/40 posmix with 4% gel and circulated to surface. United #5370.

Perfs:


Top	Bot	Thru	Comments
2471	2474		
1988	1998		
1970	1978		
1716	1721		
1696	1700		
1670	1676		

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 10-12-04
INVOICE # 2005060633