

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20662-00-00
Spot: NENWSE Sec/Twnshp/Rge: 15-23S-3W
2310 feet from S Section Line, 1740 feet from E Section Line
Lease Name: EPP A Well #: 1
County: HARVEY Total Vertical Depth: 3401 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

SURF Size: 8.625 feet: 346 225 SX CMT

\$110⁵³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/09/2004 8:00 AM

Plug Co. License No.: 5892 Plug Co. Name: BERENTZ DRILLING CO., INC.

Proposal Rcvd. from: ALAN L DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: FILL HOLE WITH ROTARY MUD TO 500' AND SPOT 35 SX CMT. FILL HOLE WITH ROTARY MUD TO 375' AND SPOT 60 SX CMT. FILL HOLE WITH ROARY MUD TO 60' AND SPOT 25 SX CMT. PUT 15 SX IN THE RATHOLE.

RECEIVED
KCC DISTRICT #2
OCT 7 - 2004

Plugging Proposal Received By: JACK LUTHI Witness Type: NONE
Date/Time Plugging Completed: 07/09/2004 5:00 PM KCC Agent: JACK LUTHI

WICHITA, KS

Actual Plugging Report:

Filled the hole with rotary mud to 500' and spotted 35 sacks of cement. Pulled drill pipe to 375' and pumped 60 sacks of cement. Pulled to 60' and pumped 25 sacks of cement. Pumped 15 sacks of cement in rathole.

60/40 posmix with 4% gel.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 11 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED #5572

Plugged through: DP

District: 02

Signed

Jack L Luthi

(TECHNICIAN)

INVOICE
DATE 10-12-04
NO. 2005060628