

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19312-00-00
Spot: NWNE Sec/Twnshp/Rge: 17-29S-15E
330 feet from N Section Line, 1650 feet from E Section Line
Lease Name: FREDONIA GAS STORAGE CH Well #: 1
County: WILSON Total Vertical Depth: 264 feet

Operator License No.: 31769
Op Name: ATMOS ENERGY CORPORATION
Address: 1301 PENNSYLVANIA ST STE 800 PEN
DENVER, CO 80203

PROD Size: 6.625 feet: 248 35 SX CMT
SURF Size: 10 feet: 20 TO SURFACE

\$ 35⁰⁰

Well Type: GSI UIC Docket No: Date/Time to Plug: 09/16/2004 8:00 AM
Plug Co. License No.: 33422 Plug Co. Name: RICK'S WELL SERVICE
Proposal Rcvd. from: MATT FRIHART Company: Phone: (615) 261-2264

Proposed Plugging Method: KILL WELL. RUN 2" WORK STRING TO BOTTOM. ESTABLISH CIRCULATION. CEMENT FROM BOTTOM TO TOP. PULL 2" AND TOP OFF CEMENT. WOC. CUT OFF SURFACE CASING BELOW FLOW DEPTH.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 09/16/2004 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The 6.625 production string was hooked onto and the well squeezed with 60 sacks of portland cement and hulls. According to plugging contractor, the well was shut in with 500-750 psi.

RECEIVED
OCT 12 2004
KCC WICHITA

RECEIVED
KCC DISTRICT #3

OCT 1 2004 AD

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

INVOICED

DATE 10-12-04
V.L. NO. 2005060635