

3 022641

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:30A.M. Day: _____ 30 Month: 9 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4.5" CASING TO 1010' THAT HAS BEEN CEMENTED

IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4.5"

CASING FULL OF CEMENT.

Plugging Proposal Received by: _____

CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All ☒ Part _____

None _____

Operations Completed: Hour: 1:30A.M. Day: _____ 30 Month: 9 2004

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4.5" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4.5" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

80 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (CONTROL NO. 20040041) (GPS SESSION PT. NO. 5.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: _____

Clayton P. Titel
TECHNICIAN

RECEIVED
OCT 12 2004
KCC WICHITA

bw