

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22179-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 6-23S-4E
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: ED LIGGETT Well #: 7
County: BUTLER Total Vertical Depth: 2545 feet

Operator License No.: 32444
Op Name: HIZEY SERVICE & SUPPLY, INC.
Address: BOX 296
AUGUSTA, KS 67010

PROD Size: 4.5 feet: 2543 100 SX CMT
SURF Size: 8.625 feet: 201 120 SX CMT

\$ 82⁷¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2004 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: MIKE KISER Company: HIZEY SERVICE & SUPPLY, INC. Phone: (316) 775-5496

Proposed Plugging Method: See actual report.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 11 2004

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #2

OCT 6 - 2004

WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: PARTIAL
Date/Time Plugging Completed: 05/25/2004 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot and pulled casing to surface. Ran 1" tubing to 250' and circulated cement to surface with 100 sacks of 60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2494	2500		

Remarks: CEMENTING BY BRADEN PETROLEUM

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

INVOICED

10-12-04
2005060630