

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21799-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 18-13S-19W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ADAMS Well #: 1-18  
County: ELLIS Total Vertical Depth: 3850 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

PROD Size: 4.5 feet: 3849 w/150 sxs cmt  
SURF Size: 8.625 feet: 257 w/170 sxs cmt

# 125<sup>13</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2004 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Emergency plug with rig over hole.  
No squeezes - casing leaks - tubing stuck at 3350'.  
Back off at 3185' - rods and pump came out.  
Perf Tech perfed at 750' - 1520' - 2100'.  
Dakota 446'-746'; Anhy 1490'-1521'; Salt 1888'-2070'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/30/2004 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Tubing in the hole at 3185'.  
Allied rigged to tubing and pumped 50 sxs 60/40 pozmix with 200# hulls mixed in.  
Pulled tubing. Perf Tech shot holes at 750' - 1520' - 2100'.  
Ran back into hole with tubing to 2100'.  
Pumped 80 sxs with 300# hulls mixed in. Had no returns.  
Pulled tubing to 1500'. Pumped 65 sxs with 100# hulls mixed in to circulate cement to surface.  
Pulled tubing and tied onto backside - pumped 50 sxs 60/40 pozmix.  
Max. P.S.I. 350#. S.I.P. 50#.  
Tied back onto 4 1/2" casing and pumped 35 sxs 60/40 pozmix.  
Shot fluid level on 10-01-2004 - 178' from surface.  
Topped off with 10 sxs cement on 10-01-2004.

Perfs:

Top	Bot	Thru	Comments
3450	3504		

Remarks: ALLIED CEMENTING COMPANY-TICKET #18858.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

HD

INVOICED

DATE 10-11-04  
JV NO. 2005060623

OCT 05 2004

