

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23420-00-00
Spot: S2N2NE Sec/Twnshp/Rge: 30-8S-17W
4290 feet from S Section Line, 1420 feet from E Section Line
Lease Name: BIRD Well #: 18
County: ROOKS Total Vertical Depth: 3440 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

SURF Size: 8.625 feet: 211

111⁸⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/25/2004 3:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 09/25/2004 4:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:


1st. Plug at 1325' w/25 sxs.
2nd. Plug at 825' w/100 sxs.
3rd. Plug at 265' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

INVOICED

DATE

10-11-04

INV. NO.

2005060625

Form CP-2/3

OCT 05 2004