

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03064-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 20-16S-11W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: JOE PRUSA Well #: 3  
County: BARTON Total Vertical Depth: 3313 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

PROD Size: 5.5 feet: 3302 150 SX CMT  
RBP Size: feet: 3111  
SURF Size: 10.75 feet: 105 100 SX CMT

\$107<sup>67</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/28/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVID M WILSON Company: KAHAN AND ASSOCIATES, INC. Phone: (918) 492-9797

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Squeeze at 1370' and 2396' w/250 sxs.  
CIBP 3111' - cement and packer cemented in at 2696'.  
Log Tech perfed at 750'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/28/2004 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Karst Well Service RIH with tubing to 2680'.  
Allied rigged up to tubing and pumped 30 sxs neat, followed with 70 sxs cement with 300# hulls mixed in.  
Pulled tubing to 1300' - pumped 85 sxs with 200# hulls to circulate cement to surface.  
Pulled tubing - tied onto 5 1/2" casing with a swedge and pumped 20 sxs cement.  
Max. P.S.I. 250#. S.I.P. 200#.  
Ran three joints into backside 94' and pumped 25 sxs to circulate cement to surface out of backside.

Perfs:

Top	Bot	Thru	Comments
3125	3233		

RECEIVED  
OCT 07 2004  
KCC WICHITA


Remarks: ALLIED CEMENTING COMPANY-TICKET #20086.

Plugged through: TBG

District: 04

10.

Signed



(TECHNICIAN)

INVOICED

DATE 10-11-04

INV. NO. 2005060626

Form CP-2/3

OCT 05 2004

**INVOICED**

20-16-11M  
NW NW NE

#3 J PHUSA

SINGLAIR PRAIRIE OIL

County BARTON

1419 BOPD

SB BM

IP

6-1-39

Comp

5-19-39

Comm

E 1850

Casing

Datum

Depth

Tops

PB 3287  
Perf 66/3161-80: A/2000

Tops	Depth	Datum
IANS	2970	
CONG	3269	
B SD	3302	
TD	3313	


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS