

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21456-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 28-9S-19W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: THYFAULT A (GILLILAND) Well #: 2  
County: ROOKS Total Vertical Depth: 3627 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 740, LB 30  
DALLAS, TX 75205

PROD Size: 4.5 feet: 3629 w/150 sxs cmt  
SURF Size: 8.625 feet: 167

*117 88*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2004 9:30 AM  
Plug Co. License No.: 7049 Plug Co. Name: RAPID WELL SERVICE INC  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-1676

Proposed Plugging Method: Ordered 400 sxs cement and 800# hulls.  
Emergency plug (holes in casing from 500' to 2400').

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/30/2004 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran in hole with tubing to 2500' - spotted 100 sxs cement with 450# hulls.  
Pulled tubing to 1150' - circulated with 145 sxs cement with 350# hulls.  
Pulled all tubing - squeezed 35 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.  
Tied to 8 5/8" x 4 1/2" annulus - squeezed 50 sxs cement.  
Max. P.S.I. 100#. S.I.P. 75#.  
Total of 330 sxs 60/40 pozmix - 10% gel and 800# hulls.

Remarks: ALLIED CEMENTING COMPANY, KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed

*100*  
Roger Z Moses

(TECHNICIAN)

INVOICE U

DATE

10-11-04

NO. NO

2005060627

Form CP-2/3

OCT 05 2004

RECEIVED  
OCT 9 2004  
KCC WICHITA

17401CFR

replacement card

JOHN B COLLINS  
HAYS KS

28-09S-19W  
NW NW NE

#2 THYFAULT

site: 1 N & 1/4 W OF ZURICH KS      city: ROOKS      API 15-163-21456  
 contr: DREILING OIL      field: ZURICH TWST  
 op: LAWRENCE F GRAY  
 fr date 10/08/81      spd date 10/12/81      drg comp 10/18/81      card issued 01/07/82      last revised 12/08/97


ELV: 2185 KB SMP	
tops.....	depth/datum
SC.....	1552 + 633
TOP.....	3126 -941
HEEB.....	3331 -1146
TOR.....	3354 -1169
LANS.....	3374 -1189
BKC.....	3587 -1402
ARB.....	3618 -1433
RTD.....	3627 -1442

**IP status:**  
 OIL, LKC, INTV NA , 12/15/82  
 INFO RELEASED: 12/8/97 - WAS OIL WELL - TEMP  
 COMP  
 CSG: 8-5/8" 167, 4-1/2" 3629 / 150 SX  
 NO CORES OR DSTS RPTD  
 MICT - CO, PF (LANS K) INTV NA, AC'D, SO, PF (LANS  
 A) INTV NA, AC'D, SO, POP, OIL WELL (POTENTIAL  
 NOT RPTD), 12/15/82 - NO OTHER INFO RELEASED BY  
 OPERATOR OR ON KCC RECORDS; ALL REQUESTS  
 FOR INFO DENIED

COPYRIGHT 1987  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS