

3 022637

To: STATE CORPORATION COMMISSION  
KCC BEN 10-12-04 SW API NUMBER 15-207-25,526 00-00  
NE,SE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION 796 feet from south section line

130 S. Market, Room 2078 3155 feet from east section line  
Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT Lease/Well# APT No: I-22

Operator License # 101 County WOODSON

Operator: STATE OF KANSAS Fee Fund Well Total Depth 1011.2 feet

Name & FEE FUND PLUGGING Production Pipe: 4.5" Size Feet 1011'

Address Surface Casing: 7" Size Feet 40'

AB oil well Gas Well SWD Well/ Input Well E-25,462 D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:30A.M. Day: 28 Month: 9 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4.5" CASING TO 1011' THAT HAS BEEN CEMENTED  
IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4.5"  
CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All X Part Technician None

Operations Completed: Hour: 11:30A.M. Day: 28 Month: 9 2004

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4.5" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4.5" CASING AT  
SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

78 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: ( CONTROL NO. 20040041 ) ( GPS SESSION PT. NO. 7. )  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
OCT 12 2004  
KCC WICHITA

I DID observe this plugging.

Signed: Clayton P. Titel  
TECHNICIAN