

3 022640

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-207-25,502 - 60-00
SE,SE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.
353 feet from south section line
2736 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# APT NO. ^A 11
County WOODSON
Well Total Depth 1120' feet

Name & FEE FUND PLUGGING
Address _____

Production Pipe: 4.5" Size Feet 1016'
Surface Casing: 7" Size Feet 45'

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-25,462 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:30A.M. Day: _____ Month: 30 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4.5" CASING TO 1016' THAT HAS BEEN CEMENTED
IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4.5"
CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 10:30A.M. Day: _____ Month: 30 2004

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4.5" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4.5" CASING AT
SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.
80 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (CONTROL NO. 20040041) (GPS SESSION PT. NO. 3.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
OCT 12 2004
KCC WICHITA

Burr