

State Corporation Commission
 Conservation Division
 Wichita State Office Bldg.
 130 S. Market, Room 2078
 Wichita, KS 67202

L PLUGGING RECORD
 C.A.R.-82-3-117

API NUMBER 15-147-20, 27500-00

LEASE NAME Graue

WELL NUMBER A-6

4950 Ft. from S Section Line

3090 Ft. from E Section Line

SEC. 2 TWP. 4 RGE. 19 (E) or (W)

COUNTY Phillips

Date Well Completed 8-15-1980

Plugging Commenced 12-10-96

Plugging Completed 12-10-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc.

ADDRESS Box 428 Logan, KS 67646

PHONE#(913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-17-96 (date)

by Dennis Hamel - Hays (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation KC Depth to Top 3186 Bottom 3378 T.D. 3410

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
-	SAND + Shale	Surface	220	8 5/8	220	None
-	Shale and limestone	Surface	3401	4 1/2	3401	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Perforated well at 1540' and 980'. Then pumped 25 sacks cement with 2 sacks of Hulls followed by 10 sacks gel followed by 100 sacks cement. Max pressure 500 PSI. BSIP equal to 200 PSI Pumped down 8 1/2" with 1 sack Hulls followed by 25 sacks cement. 100 PSI BSIP.

Name of Plugging Contractor Allied Cementing Co. Inc License No. 12-13-96

Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc.

STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428 Logan, KS 67646

11th day of DECEMBER, 19 96

Robert B. Hartman
 Notary Public



My Commission Expires: 3/29/99

USE ONLY ONE SIDE OF EACH FORM