

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15-147-20,261 ⁰⁰⁻⁰⁰

LEASE NAME Ehm

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2290 Ft. from S Section Line

4930 Ft. from E Section Line

SEC. 2 TWP. 4S RGE. 19W (E) or (W)

COUNTY Phillips

Date Well Completed 11-12-79

Plugging Commenced 10-25-94

Plugging Completed 10-25-94

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 10-25-94 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 Filed? yes If not, is well log attached? _____

Producing Formation L/KC Depth to Top 3208' Bottom 3428' T.D. 3428'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	201'	None
				4 1/2"	3423'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Shot two holes in casing, one at 925' & one at 1500'. Pumped 212 sx of 60/40 Poz, 10% gel & 500# hulls down 4 1/2" casing, 500# max, 200# shut-in pressure. Tied on to 4 1/2" backside and pumped 100 sx of same cement down backside with 100# max, 100# shut-in pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corp. License No. 5128

Address 207 West 12th St. Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Oper. Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan Nixon (Employee of Operator) or (Operator) of above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 207 W. 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 30th day of November 1994

[Signature]
Notary Public

My Commission Expires: 5-24-97



RECEIVED
STATE CORPORATION COMMISSION
DEC 01 1994
EXPLORATION DIVISION
WICHITA, KANSAS
12-1-94
Form CP-4
Revised 05-88