

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15-147-20,377-00-01

LEASE NAME Ehm

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3 Injection

1980 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 2 TWP. 4S RGE. 19W (E)or(W)

COUNTY Phillips

Date Well Completed 05-10-82

Plugging Commenced 10-24-94

Plugging Completed 10-24-94

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well Injection Docket # E-20,066

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 10-24-94 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 Filed? yes If not, is well log attached? _____

Producing Formation L/KC Depth to Top 3222' Bottom ≈3442' T.D. 3450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	212'	None
				4 1/2"	3448'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Perforated 3 holes at 1546'. Ran tubing to 2512' and pumped 50 sx of common cement w/100# hulls. Pulled tubing to 1575', pumped 125 sx 60/40 Poz, 10% gel w/200# hulls, well circulated. Came out w/tubing & pumped 50 sx cement down 4 1/2" casing. Max and shut-in pressure was 500#. Could not pump into 4 1/2" backside at 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corp. License No. 5128

Address 207 West 12th St. Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Oper. Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan Nixon (Employee of Operator) or (Operator) of above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 W. 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1994

Roxie VonIntel
Notary Public

My Commission Expires: 5-24-97

