

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00570-00-00

API NUMBER 6-4-64 COMP

LEASE NAME BISHOP

WELL NUMBER 1

SPOT LOCATION C SE NW

SEC. 3 TWP. 4 RGE. 19 (P) or (M)

COUNTY PHILLIPS

Date Well Completed 6-4-84

Plugging Commenced 10-12-85

Plugging Completed 10-16-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R P NIXON OPERATIONS

ADDRESS 207 W 12TH HAYS KS 67601

PHONE # (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS-DALE BALTHAZAR

Is ACO-1 filed? YES If not, is well log attached?

Producing formation Depth to top bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
SURFACE		208	surf	8 5/8"	208'	NONE
PRODUCTION		3437	surf	4 1/2"	3437'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Cemented back side with 150 sx of 60-40 pozmix 6% gel 3% c.c. (no pressure) Rained out and pulled off location. Cemented with 25 sx, 1 hull, 25 sx, 10 gel, 1 hull, released plug and capped with 100 sx cement. (60-40 pozmix 6% gel mix) Perforated anhydrite at 1550' with 1 hole 450 psi casing pressure, 350 psi on 8 5/8" Completion time 10:40 10-16-85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor JAY-LAN CORPORATION License No. 719

Address 207 W 12TH HAYS KS 67601

STATE OF KANSAS COUNTY OF ELLIS, ss.

DAN A NIXON (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

RECEIVED
1023-85
OCT 23 1985

(Signature) *Dan Nixon*

(Address) 207 W 12TH HAYS KS

CONSERVATION DIVISION
Wichita, Kansas



LORNA M. HERRMAN
NOTARY PUBLIC
STATE OF KANSAS

SUBSCRIBED AND SWORN TO before me this 22 day of OCTOBER, 1985
Lorna M. Herrman
Notary Public

MY APPT. EXPIRES 6-19-88

My Commission expires: