

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-147-20, 227-00-00

LEASE NAME Beckman "B"

WELL NUMBER 1

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 4 RGE. 19 (E) or (W)

COUNTY Phillips

Date Well Completed Aug. 1977

Plugging Commenced Sept. 22, 1989

Plugging Completed Sept. 22, 1989

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Petroleum Management Inc.

ADDRESS 400 N. Woodlawn, #201, Wichita, KS 67208

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 21, 1989 (date)

by District #4, Hays (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No, log sent w/plugging application

Producing Formation LKC Depth to Top 3205 Bottom 3430 T.D. 3445

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	0'	242'	8 5/8"	242'	0'
		0'	3442'	4 1/2"	3442'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Producing perforations plugged back. Well perforated at 967' and 1527'. Pumped 250 sx cement w/250# hulls down 4 1/2". Pumped 100 sx cement and 250# hulls down surface casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management Inc. License No. 5242

Address P.O. Box H Plainville, KS


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PMI

STATE OF Kansas COUNTY OF Sedgwick, ss. DEC 21 1989

Steven P. O'Neill (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well and as filed that the same are true and correct, so help me God.

(Signature) Steven P. O'Neill

(Address) 400 N. Woodlawn, Suite 201 Wichita, KS 67208



AND SWORN TO before me this 19th day of December, 1989

Bonnie Brown  
Notary Public

My Commission Expires: March 1, 1993