

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22473-00-00  
Spot: NENESE Sec/Twnshp/Rge: 29-8S-24W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: KEITH A Well #: 1  
County: GRAHAM Total Vertical Depth: 4413 feet

Operator License No.: 31933 4419

CIBP Size: feet: 3750

Op Name: M E KLEIN & ASSOCIATES, INC

PROD Size: 5.5 feet: 4438 435 SX CMT

Address: PO BOX 721436

SURF Size: 8.625 feet: 225 250 SX CMT

NORMAN, OK 73070 Bear Petroleum PO Box 438 HAYSVILLE KS, 67060

\$143<sup>42</sup>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/13/2004 10:00 AM

Plug Co. License No.: 33346

Plug Co. Name: TR SERVICE AND RENTAL, INC.

Proposal Rcvd. from: CARL ZIMMERMAN

Company: M.E. KLEIN & ASSOCIATES, INC.

Phone: (785) 625-1102

Proposed Plugging Method:

Ordered 190 sxs cement - 22 sxs gel - no hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/13/2004 2:30 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 3750' - spotted 22 sxs gel with 20 sxs cement.  
Pulled tubing to 1275' circulated with 95 sxs cement.  
Pulled all tubing and squeezed with 75 sxs cement.  
Max. P.S.I. 400#. S.I.P. 400#.  
Tied to 8 5/8" x 5 1/2" annulus - pressured to 250# - took no cement.  
Total of 190 sxs 60/40 pozmix - 10% gel - 20 sxs gel and no hulls.

Top	Bot	Thru	Comments
3938	3942		
3856	3860		
2918	3920		

RECEIVED  
AUG 25 2004  
KCC WICHITA

Remarks: COPELAND ACID & CEMENT. HOXIE TANK-WATER.

Plugged through: TBG

District: 04

Signed

Regan D. Moses  
(TECHNICIAN)

INVOICED

DATE 8-26-04

INV. NO. 2005060405

AUG 19 2004

BURCH EXPLORATION, INC  
PARKER, CO 80134

29-08 -24W  
NE NE SE

#1 KEITH "A"

site: 1 S & 3 E OF MORLAND, KS      city: GRAHAM      API 15-065-22473  
contr: WESTERN KANSAS DRILLING      field: HOLLEY NORTH  
geol: RON MACKEY

dr	spc	drig	card	last
date 07/06/88	date 07/05/88	comp 07/15/88	issued 03/01/89	revised 03/01/89


ELV: 2407 KB LOG
tops.....depth/datum
ANH.....2103 +304
HEEB.....3687 -1280
TOR.....3713 -1306
LANS.....3726 -1319
BKC.....3951 -1544
PBTD.....3970 -1563
RTD.....4413 -2006

IP status:  
OIL, P 73 BO & 20 BWPD, LKC 3802-3942 OA,  
CSG: 8-5/8" 225 / 250 SX, 5-1/2" 4438 / 435 SX  
NO CORES  
DST (1) 3747-3763 (LKC), / 15-30-30-45, REC 30' FREE  
OIL, 120' OCWM, 180' OCW ISIP 1227# FSIP 2027#  
IFP 86# -100# FFP 144# -182# IHP 2083# FHP 2027#  
DST (2) 3761-3788 (LKC), / 20-40-60-75, REC 45' FREE  
OIL, 60' OCWM, 240' OCW ISIP 1242# FSIP 1221# IFP  
77# -94# FFP 127# -199# IHP 2121# FHP 2175#  
DST (3) 3793-3803 (LKC), / 20-40-70-80, REC 2' FREE  
OIL, 28' OCM ISIP 1082# FSIP 1077# IFP 48# -48#  
FFP 54# -54# IHP 2092# FHP 2044#

COPYRIGHT 1989  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

BURCH EXPLORATION, INC  
PARKER, CO 80134

29-08 -24W  
NE NE SE

#1 KEITH "A"

DST (4) 3835-3860 (LKC), / 15-30-45-60, 240' GIP, REC 25' FREE OIL, 95' OCM, 240' W ISIP  
1288# FSIP 1288# IFP 104# -123# FFP 130# -196# IHP 2127# FHP 2100#  
DST (5) 3886-3908 (LKC), / 10-20-20-30, REC 60' OCWM, 240' OCMW, 960' W ISIP 1200#  
FSIP 1114# IFP 173# -211# FFP 278# -403# IHP 2046# FHP 2036#  
DST (6) 3912-3927 (LKC), / 15-30-30-45, 280' GIP, REC 160' FREE OIL, 120' OCMW, 240' SW  
ISIP 1268# FSIP 1254# IFP 119# -134# FFP 172# -235# IHP 2161# FHP 2137#  
MICT - CO, PF (LKC) 3938-3942, W / 4 SPF, AC 200 GAL (15% NE), SO, PF (LKC) 3918-3920, W /  
4 SPF, AC 100 GAL (15% NE), SO, PF (LKC) 3856-3860, W / 4 SPF, AC 200 GAL (15% NE), SO,  
PF (LKC) 3802-3864, W / 4 SPF, AC 1100 GAL (15% NE), SO, SET 2-7/8" TBG AT 3841, POP, P  
73 BO & 20 BWPD (GR 27), 8/18/88