

4 060094

6-21

TA: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-147-20,513-00-00
SE NW, SEC. 16, T 4 S, R 20 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923
Operator: American Petroleum Co., Inc.
Name & Address 7701 E. Kellogg, Suite 240
Wichita, KS 67207
316-686-1635

Lease Name Becker Well # 1
County Phillips 116.03
Well Total Depth 3570 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address Russell, KS

Company to plug at: Hour: 10:00AM Day: 21 Month: June Year: 19 90

Plugging proposal received from John Carlin
(company name) Emphasis Oil Operations (phone) _____

were: Order 190 sxs. 60/40 pos 6% gel 1/4 flocele per sx.
Space all plugs with heavy drill mud through drill pipe.

Arbuckle not reached. TD at BKC

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXX

Operations Completed: Hour: 10:00AM Day: 21 Month: June Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1675' with 25 sxs. Anhydrite 1662-1687'
2nd plug at 990' with 100 sxs. Dakota 686-986'
3rd plug at 300' with 40 sxs. Surface pipe to 250'
4th plug at 40' with 10 sxs.
rathole with 15 sxs.

Remarks: Halliburton Cementing-Oberlin
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-27-90
INV. NO. 28499

Signed Herb Deines
(TECHNICIAN)

Herb Deines