

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00879-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 1-12S-23W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: NEWCOMER Well #: 21
County: TREGO Total Vertical Depth: 3783 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 5893 SADDLE CREEK TRAIL
PARKER, CO 80134

PROD Size: 4.5 feet: 3782 w/500 sxs cmt
SURF Size: 8.625 feet: 330 w/215 sxs cmt

#122 95

Well Type: ~~OIL~~ FOR *KCC SEN 10-5-04* UIC Docket No: E16356.4 Date/Time to Plug: 09/01/2004 8:30 AM
Plug Co. License No.: 32810 *Wichita KCC* Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC

Proposal Rcvd. from: JIM SCHOENBERGER Company: SHELBY RESOURCES, LLC Phone: (785) 483-8027

Proposed Plugging Method: Ordered 150 sxs cement - 13 sxs gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2004 3:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 3600' - spotted 30 sxs cement with 300# hulls - 13 sxs gel and 200# hulls.
Pulled tubing to 1500' - circulated with 60 sxs cement at 1200 P.S.I.
Pulled all tubing and topped off with 10 sxs cement.
Total of 100 sxs 60/40 pozmix - 10% gel - 13 sxs gel - 500# hulls.

Remarks: LEASE ALSO KNOWN AS RINKER #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Roger & Moses
(TECHNICIAN)

INVOICED

DATE

10-5-04

INV. NO.

2005060594

SEP 21 2004

TEXACO INC.

#1 RINKER

1-12-23W
NW SW NE


Contr. LEBEN DRILLING

TREGO County

E 2428KB Comm. 4/11/63 Comp. 5/23/63 IP CO PMP 35 BOPD + 2 1/2
BWPD/LANS 3742-47

LOG Tops	Depth	Datum
HEEB	3634	-1206
TOR	3656	-1228
LANS	3668	-1240
LTD	3768	-1340
RTD	3783	-1355

Casing
 8" 330/215 sx:
 4" 3782:
 CO 3761: 12/3723-27: FU 250' SW/1
 HR: SWB 30 GW/2 HRS: FU 500' SW
 12 HRS: 9/3710-13: SWB DRY: 15/
 3742-47: SWB 48 GO, TR WTR/4
 HRS: A 375 (3710-13) A 500:
 (3742-47) SWB 10 B A WTR + 52
 B LD WTR/3 HRS: SWB 5 BO + 99 B
 WTR/7 HRS: SWB 1 1/5 BO + 10 1/2 B
 WTR/2 HRS: SWB 16 BO + 6 1/2 BW/
 6 HRS: (3742-47): SQZD 3710-13
 & 3723-27/50 sx: CO 3760: SWB
 NEW COMER EXT 17 BO + 7 BW/9
 HRS: (3742-47):
 POP:



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INDEXED