

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21085-00-00
Spot: NESE Sec/Twnshp/Rge: 11-26S-9W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: REECE Well #: 1
County: RENO Total Vertical Depth: 3750 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

PROD Size: 4.5 feet: 3699 125 SX CMT
SURF Size: 8.625 feet: 302 225 SX CMT

\$ 121⁸⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/09/2004 9:30 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF Company: SHAWNEE WELL SERVICE, INC. Phone: (620) 254-7893

Proposed Plugging Method: CIBP 3145' & 2 sxs of common; 1400' & 35 sxs; 850' & 35 sxs; and 350' to 0'.

RECEIVED
KCC DISTRICT #2
SEP 21 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2004 1:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 3145' and 2 sacks of common cement. Shot 4-1/2" casing off at 2014'. Pulled to 1400' and pumped 35 sacks of cement. Pulled to 850' and pumped 35 sacks of cement. Pulled to 350' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3504	3508		

RECEIVED
OCT 06 2004
KCC WICHITA

Remarks: ACID #8710

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

DATE 10-6-04
INV NO 2025060608