

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20175-00-01
Spot: SWNE Sec/Twnshp/Rge: 17-19S-10W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: MANSZ Well #: 1
County: RICE Total Vertical Depth: 3329 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 513 W. 6TH ST
ELLINWOOD, KS 67526

CIBP Size: feet: 3258
PROD Size: 5.5 feet: 3316 125 SX
SURF Size: 8.625 feet: 213 175 SX

4/08¹⁹

Well Type: EOR UIC Docket No: E22507.1 Date/Time to Plug: 09/16/2004 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Sand to 3030' & 5 sxs; 1300' & 35 sxs; 850' & 35 sxs; and 270' - 0.
Plugging Method:

RECEIVED
KCC DISTRICT #2
SEP 21 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2004 12:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3030' and 5 sacks of common cement. Perforated the casing at 1300', 850', and 270'. Ran tubing to 1300' and pumped 35 sacks of cement. Pulled to 850' and pumped 35 sacks of cement. Pulled 270' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3181	3186		
3081	3086		

RECEIVED
OCT 06 2004
KCC WICHITA

Remarks: ALLIED #17700

Plugged through: TBG

District: 02

Signed Jack Luthi
(TECHNICIAN)

INVOICED

DATE 10-6-04

INV. NO. 2005260607